



icmr
INDIAN COUNCIL OF
MEDICAL RESEARCH

NIRBI
NATIONAL INSTITUTE FOR
RESEARCH IN BACTERIAL INFECTIONS

आई. सी. एम. आर. - राष्ट्रीय जीवाणु संक्रमण अनुसंधान संस्थान

ICMR - NATIONAL INSTITUTE FOR RESEARCH IN BACTERIAL INFECTIONS

Formerly, ICMR-National Institute of Cholera and Enteric Diseases (ICMR-NICED)

स्वास्थ्य अनुसंधान विभाग, स्वास्थ्य एवं परिवार कल्याण मंत्रालय, भारत सरकार

Department of Health Research, Ministry of Health & Family Welfare, Govt. of India

WHO COLLABORATING CENTRE FOR RESEARCH AND TRAINING ON DIARRHOEAL DISEASES

Ref.: NIRBI/Stores/D-3/Repairing/2025-26

Date : 26.09.2025

Quotation Enquiry

Sealed quotations are invited on behalf of Director, ICMR-NIRBI, Kolkata for **urgent repairing** of NIRBI 1 Room No 403, 404, 405, 406 & JICA data Management Room. Interested vendors are requested to quote your lowest competitive rates for the following works alongwith GST in the company letter head as per give format:

Sl. No.	Location	Description of Item	Quantity	Unit
1	NIRBI 1 & JICA	Removing white or color wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	510	Sqm
2	NIRBI 1	Repair to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sqm and under, including cutting the patch in proper shape, raking out joints and preparing plastering the wall surface with white cement based polymer modified self curing mortar, including disposal of rubbish, all complete as per the direction of Engineer-In-Charge.	2	Sqm
3	NIRBI 1 & JICA	Wall painting with acrylic emulsion paint, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour. Two Coat	510	Sqm
4	NIRBI 1 & JICA	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colors, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	4	Sqm
5	NIRBI 1 & JICA	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	70	Sqm
6	NIRBI 1 & JICA	Applying priming coats with primer of approved brand and manufacture, having low VOC (Volatile Organic Compound) content. With water thinnable cement primer on wall surface having VOC content less than 50 grams/litre	510	Sqm
7	JICA	First Dismantling Side partition wall then supply and making one open partition with gypsum board with one flush door of 35 mm with sal wood frame as per site condition prevails decorative finish, along with etching glass stripe window frame to be make with teak wood frame, all covered portion with having frame of teak wood. Finishing with varnishing and full complete job.	1	Job
8	NIRBI 1	Rewiring of fan light point with 1.5sqmm FRLS pvc insulated copper conductor single core cable as earth/conducting wire in existing pvc conduit and dismantling as required Group C	50	Point
9	NIRBI 1	Supplying and fixing 5/6 amps modular switch on the existing modular plate& switch box including connection but excluding modular plate	40	Nos
	NIRBI 1	Supply and installation of 20 W Round LED recessed panel light with Complete wiring to switches.	10	Nos



पी-33, सी.आई.टी. रोड, स्किम - XM, बेलियाघाटा, कोलकाता - 700 010, पश्चिम बंगाल, भारत

P-33, C.I.T. Road, Scheme - XM, Beliaghata, Kolkata - 700 010, West Bengal, India



+91-33-2363 3373 (निदेशक/Director), +91-33-2370 1176, 5533 (प्रशासन/Administration)




www.niced.org.in

10	NIRBI 1	Supplying and fixing 8 Module PVC/GI Box along with module base & cover plate for modular switch in recess etc as required	4	Nos
11	NIRBI 1	Supplying installation testing and commissioning of 20 W LED batten having lumen efficiency not less than 100 Lumen/Watt, THD< 10%,PF>0.90,CRI>80 to be installed on the wall/ceiling, connection with 1.5 sqmm FRLS PVC insulated copper conductor, single core cable.	16	Nos
12	NIRBI 1	Supplying, installation, testing and Commissioning of 20 w Square/ Circular true ceiling LED light	16	Nos
13	NIRBI 1	Supply, Installation, testing and Commissioning of 1200 mm ,single phase 3 blade 5 star rated BLDC motor ceiling fan, shackle kit, down rod, a pair of canopies, remote with batteries. With 3 year warranty	8	Nos

Terms & Conditions:

1. The Director, ICMR-NIRBI reserves the right to accept or reject the quotations without assigning any reasons thereof.
2. Any decision taken by the Director, ICMR-NIRBI at any point of time in connection with this process shall be final and conclusive and no claim or dispute from any query in this regard shall be entertained.
3. No advance payment will be made. The payment will be made on rendering the services availed and satisfactory report of the end user(s).
4. No extra payment on account of transportation, handling, loading, unloading, labour charges etc. will be made. However, GST as per rules will be permissible.
5. While submitting the quotations the rate against each work and net amount to be paid, GST etc. should be specified separately.
6. ICMR-NIRBI, Kolkata does not bind itself to accept the lowest quote and reserves the right to accept the same in part or full.
7. Please ensure that the supply is as per the specification.

Sealed quotations super scribed as **"Repairing work of NIRBI 1 Room No 403, 404, 405, 406 & JICA data Management Room"** must be dropped in tender box proved at ICMR-NIRBI-I Building by **16.10.2025 till 05.00 PM**. The last date may be extended subject to requirement.


 26/9/2025
 Store-in-Charge
 Store-2